

**PRE-BID M.O.M. FOR S.S. RAILING WORK AT VARIOUS STAIRCASES IN OFFICE CAMPUS,
PASHAN, PUNE.
TENDER NOTICE NO. : IITM/CE/Railing work/2016-17/05**

A Pre bid meeting for the subject work held on 14/07/2016 at 1100 hrs in Aryabhata hall at IITM, Pune. During the discussion with vendors present in the meeting the following decision were taken by the committee:

Sr. No.	Point discussed	Reference	Decision taken
1.	Bifurcation of S.S quantity for each type of railing and tentative Reference Drawing of S.S railing to be provided	BOQ	There are mainly two type of S.S RAILINGS are considered in tender BOQ as per enclosed Drawing for S.S railing - Annexure-I and vendors shall quote their rates as per revised BOQ- Annexure-II wherein the Bifurcation of S.S quantity for each type of railing now mentioned.
2.	Details of railing sections	Commercial BOQ	A. thickness for 50mm, 40mm, 25mm pipe to be considered 2.77mm B. Thickness of rectangular section to be considered 1.2mm C. Thickness of base plate to be considered 5mm
3.	Payment terms and date of completion	Clarifications were Asked by vendors	No change. As per tender document.
4.	Mock up	Pre-bid discussion	Successful bidder will prepare the mockup for Client approval
5.	What taxes shall be deducted from bill?	Asked by vendors	As per Standard Govt. procedure the tax deductions viz. W.C.T, T.D.S and Labour cess etc will be made from contractor bill and certificate for the same will be issued on demand from client to Contractor for reimbursement purposes in any.
6.	Completion period	Tender Document	No change. As per tender document.
7.	Bid Submission	Tender Document	Technical Bid Envelope: Forwarding letter, copy of pre bid M.O.M., complete tender documents, company profile, bank details for RTGS, details of work experience for similar contracts completed/in hand, related documents as mentioned in tender duly signed and stamped on each page, EMD & tender fee. Commercial Bid Envelope: Duly filled and signed. Bidder should submit their commercial bid as per BOQ as enclosed along with pre bid MOM.

- NOTE:** 1) Bid should be submitted on or before due date and time i.e.27.07.2016 at 12:30hrs
2) Bid received after due date and time will be rejected.
3) Bidder should submit their commercial bid a per revised BoQ as enclosed along with Pre-Bid MoM.



Annexure II

Revised BoQ for railing work at various staircases in IITM Pune.

Sr. No.	Description	QTY	UNIT	BASIC RATE	Taxes		Total rate Rs.	AMOUNT
					Vat	Service tax		
1	Providing and fixing brush finish stainless steel (Grade 304) railing made of Hollow tubes, rectangle, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners , stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-in-charge. (for payment purpose only weight of stainless steel members shall be considered including fixing accessories such as nuts, bolts, fasteners, plates etc.)							
1.1	Rectangular section	150	kg					
1.2	Pipe section	4150	kg					

Total =



